




\\GTH-AD1\Building\Town Engineer\G_2023\2023.G04\dwg\Mountain Road_CIVIL000.dwg






STORM SEWER TRENCH DETAIL

(NOT TO SCALE)




RIP RAP CHANNEL DETAIL

(NOT TO SCALE)



ELECTRICAL CONDUIT TRENCH DETAIL

(NOT TO SCALE)



CURLEX ® SEDIMENT LOG STAKE DETAIL (ON BARE SOIL)

(NOT TO SCALE)

GRANBY, CONNECTICUT SCALE: NONE NO. DATE DESCRIPTION **GRANBY, CONNECTICUT 06035** PHONE: (860) 844-5318 FAX: (860) 844-5325 REVISIONS

PAVED ROAD LENGTH = AS SHOWN ON PLAN (MIN.=30') OR DRIVE WIDTH = AS SHOWN ON PLAN (MIN. =12') REMOVE TOPSOIL & ORGANICS CONNDOT No. 3 PRIOR TO PLACING GEOTEXTILE CRUSHED GRAVEL & STONE

CONSTRUCTION ENTRANCE DETAIL (CE)

(NOT TO SCALE)

NOTES & DETAILS TOWN OF GRANBY ACCESS DRIVE TO COMMUNICATIONS TOWER 239 MOUNTAIN ROAD

JOB #: 2023.G04 SHEET: 4 OF 6 DATE: September 5, 2025

TOWN OF GRANBY ENGINEERING DEPARTMENT **GRANBY TOWN HALL** 15 NORTH GRANBY ROAD

GENERAL NOTES:

- 1. THE CONTRACTOR SHALL USE "CALL BEFORE YOU DIG, 1-800-922-4455" PRIOR TO ANY CONSTRUCTION ACTIVITY.
- 2. CONSTRUCTION METHODS AND MATERIALS, SHALL CONFORM TO THE REGULATIONS OF CONNDOT FORM 819 AS AMENDED.
- 3. THE CONTRACTOR SHALL VERIFY ALL LINES AND GRADES PRIOR TO ANY CONSTRUCTION. ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AND INCURRING THE COST OF ALL REQUIRED PERMITS, INSPECTIONS, CERTIFICATES, ETC.
- THE CONTRACTOR IS SOLELY RESPONSIBLE FOR JOBSITE SAFETY AND SHALL COMPLY WITH ALL FEDERAL AND STATE OCCUPATIONAL SAFETY AND HEALTH AUTHORITY (O.S.H.A.) REGULATIONS.
- THE CONTRACTOR SHALL PROVIDE, INSTALL, MAINTAIN AND REMOVE ALL SHORING, BRACING AND OTHER ITEMS NECESSARY TO RETAIN BANKS OR EXCAVATIONS AND PREVENT CAVE-INS AND DISPLACEMENT OF ADJOINING GROUND. SHORING AND
- BRACING SHALL BE ENTIRELY INDEPENDENT OF FOOTINGS. THE CONTRACTOR SHALL KEEP TRENCHES FREE FROM STANDING WATER AT ALL TIMES UNTIL PERMANENT WORK IS IN PLACE. ALL NECESSARY WELL-POINTING AND/OR PUMPING SHALL BE PERFORMED AND MAINTAINED AT THE CONTRACTOR'S
- ALL DISTURBED AREAS ARE TO RECEIVE SIX (6) INCHES OF TOPSOIL AND SEED UNLESS OTHERWISE SHOWN. SEED TO BE ONE OF THE TYPES NOTED ON THIS SHEET. SEED TYPES (NO.) NOT TO BE MIXED.
- 9. ALL EXPOSED CURB ENDS ARE TO BE TAPERED.
- 10. SAW CUT EXISTING CURBS AND PAVEMENT WHERE THEY MEET PROPOSED CURBS OR PAVEMENT.
- PROPERTY LINE INFORMATION TAKEN FROM A CLASS A-2, T-2 SURVEY ENTITLED," BOUNDARY PLAN, PREPARED FOR BRIAN SCOTT PIERCE TRUSTEE, 229 MOUNTAIN ROAD, GRANBY, CONNECTICUT, SCALE: 1"=80', DATE: 9/18/24, DENNO LAND SURVEYING AND CONSULTING, LLC."

GENERAL EROSION AND SEDIMENT CONTROL NOTES:

- EROSION AND SEDIMENT CONTROL MEASURES SHALL CONFORM TO, "CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL, THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION, EFFECTIVE MARCH 30, 2024," AS
- THE SEDIMENT AND EROSION CONTROL NOTES AND DETAILS INCLUDED IN THE CONSTRUCTION DOCUMENTS MAY REFER TO INFORMATION LOCATED IN THE GUIDELINES. THE CONTRACTOR SHALL HAVE A COPY OF THE GUIDELINES AVAILABLE FOR REFERENCE DURING CONSTRUCTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION, MAINTENANCE, AND REMOVAL OF ALL SEDIMENTATION AND
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING THE NEARBY STREETS OF ANY SEDIMENT OR CONSTRUCTION DEBRIS ORIGINATING FROM THIS PROJECT.
- EXCESS SOIL MATERIAL FROM THE PROPOSED CONSTRUCTION IS TO BE REMOVED FROM THE SITE. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FOR ITS DEPOSITION.
- THE CONSTRUCTION ENTRANCE, IF NOTED, AND THE SEDIMENT CONTROLS LOCATED AT THE PERIMETER OF THE PROPOSED EDGE OF DISTURBANCE(S), SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION ACTIVITY. INSTALLATION SHALL BE AS PER THE MANUFACTURERS' INSTRUCTIONS AND AS DETAILED ON THESE PLANS.
- ALL STORM DRAINAGE INLETS ARE TO BE PROTECTED FROM SEDIMENT INTRUSION. SEDIMENT SHALL BE REMOVED FROM ALL DRAINAGE STRUCTURES, PIPE SYSTEMS, OUTLET STRUCTURES, RIP RAP, AND CHANNELS.
- ALL STOCKPILES OF SOIL ARE TO BE ENCIRCLED WITH SILT FENCE.
- THE CONTRACTOR SHALL EMPLOY TEMPORARY EROSION CONTROL MEASURES SUCH AS, SILT FENCE, SEDIMENT LOGS, STONE BARRIERS, EROSION CONTROL MATTING, SEDIMENT TRAPS, DEWATERING BASINS, AND TEMPORARY STORMWATER DIVERSIONS, AS NECESSARY DURING CONSTRUCTION, TO PROTECT THE SITE AND ADJACENT PROPERTIES FROM EROSION.
- 10. ALL LOCATIONS, INCLUDING SWALES, LAWN AREAS, AND STORM SEWER DISCHARGE POINTS, THAT ARE TO RECEIVE A CONCENTRATED FLOW OF STORMWATER, ORIGINATING FROM SURFACE FLOW OR STORM SEWER SYSTEMS, SHALL BE STABILIZED AND PROTECTED FROM EROSION PRIOR TO RECEIVING THE WATER.
- DAMAGED SECTIONS OF SEDIMENT BARRIERS SHALL BE REPLACED BY THE CONTRACTOR. SEDIMENT DEPOSITS SHALL BE REMOVED BY THE CONTRACTOR WHEN THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER. SEDIMENT SHALL BE REMOVED IN A MANNER THAT DOES NOT CAUSE ADDITIONAL EROSION OR POLLUTION.
- 12. AT A MINIMUM, ALL SEDIMENT CONTROL MEASURES SHALL BE INSPECTED BY THE CONTRACTOR AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL AMOUNT OF 0.5 INCHES OR GREATER. REPAIR SEDIMENT CONTROL MEASURE AS NECESSARY.
- 13. DISTURBED AREAS ARE TO BE STABILIZED AS SOON AS POSSIBLE AFTER DISTURBANCE. WHEN GRADING OF THE DISTURBED AREA WILL BE SUSPENDED FOR A PERIOD OF 30 OR MORE CONSECUTIVE DAYS, BUT LESS THAN 5 MONTHS, STABILIZE THE SITE WITHIN 7 DAYS OF THE SUSPENSION OF GRADING THROUGH THE USE OF MULCH OR OTHER MATERIALS APPROPRIATE FOR USE AS A TEMPORARY SOIL PROTECTOR. FOR SURFACES THAT ARE NOT TO BE REWORKED WITHIN 5 MONTHS BUT WILL BE REWORKED WITHIN 1 YEAR, USE TEMPORARY SEEDING, MULCH FOR SEED OR WHEN SLOPES ARE LESS THAN 3:1, WOOD CHIPS, BARK CHIPS OR SHREDDED BARK. FOR SURFACES THAT ARE TO BE REWORKED AFTER 1 YEAR, USE PERMANENT SEEDING AND MULCH FOR SEED.
- EXCAVATED STUMPS AND CUT TREES ARE TO BE REMOVED TO AN OFF-SITE DISPOSAL AREA. BRUSH AND SLASH ARE TO BE CHIPPED AND STOCKPILED FOR FUTURE USE OR SPREAD ON THE SITE AS DIRECTED. EXCAVATED STUMPS, CUT TREES, BRUSH, AND SLASH, ARE NOT TO BE BURIED ON-SITE.

PROJECT NARRATIVE:

THE PROPOSED PROJECT CONSISTS OF THE CONSTRUCTION OF A NEW COMMUNICATIONS TOWER WITH AN ACCESS DRIVE AND ASSOCIATED IMPROVEMENTS. THE PROJECT AREA IS LOCATED AT 239 MOUNTAIN ROAD ON PROPERTY ACQUIRED BY THE TOWN OF GRANBY. THE SITE CONTAINS 5.49 ACRES AND IS MOSTLY WOODED. THE SITE SLOPES UP TO THE SOUTH FROM MOUNTAIN ROAD.

THERE ARE NO INLAND WETLAND SOILS OR WATERCOURSES ON THE SITE. THE SOILS ARE PAXTON AND MONTAUK FINE SANDY LOAMS. THESE ARE WELL DRAINED SOILS. SEVEN TEST HOLE WERE EXCAVATED TO DETERMINE THE DEPTH TO BEDROCK. THE DEPTH VARIED FROM NOT ENCOUNTERED TO AS SHALLOW AS EIGHTEEN INCHES. STORMWATER FROM THE SITE DRAINS TO MOUNTAIN ROAD WHERE IT IS COLLECTED INTO CATCH BASINS AS PIPED NORTH TO THE OPPOSITE SIDE OF THE ROAD.

APPROXIMATELY 1.71 ACRES OF THE SITE SITE AND THE ADJACENT FRONTAGE ALONG MOUNTAIN ROAD WILL BE DISTURBED BY CONSTRUCTION. STORMWATER WILL BE COLLECTED ON THE EAST SIDE OF THE PROPOSED DRIVE IN A SWALE, AND COLLECTED IN A "DG" ENDWALL. IT WILL THEN BE PIPED TO AN EXISTING HEADWALL STRUCTURE. THE APPLICANT IS PROPOSING MITIGATION MEASURES IN AREAS SHOWN ON THE PLANS. THIS WILL CONSIST OF THE FOLLOWING:

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES WILL BE IMPLEMENTED DURING CONSTRUCTION. THE ANTICIPATED CONSTRUCTION WILL BEGIN IN THE FALL OF 2025 AND BE COMPLETED BY 2026.

THE RESPONSIBLE PARTY IS:

KIRK A. SEVERANCE DIRECTOR OF PUBLIC WORKS. 52 NORTH GRANBY ROAD GRANBY, CT 06035 PHONE: (860) 653-6535

OVERALL CONSTRUCTION SEQUENCE:

- 1. FLAG THE LIMITS OF CONSTRUCTION AND TREE CLEARING.
- 2. INSTALL PERIMETER EROSION AND SEDIMENT CONTROLS.
- 3. SITE MEETING WITH TOWN ENGINEER.
- 4. CUT TREES WITHIN THE CLEARING LIMITS AND REMOVE CUT WOOD. REMOVE AND DISPOSE OF STUMPS.
- 5. STRIP AND STOCKPILE THE EXISTING TOPSOIL AND OTHER SURPLUS MATERIAL. STABILIZE THE STOCKPILE(S).
- 6. ROUGH GRADE THE DRIVE ENTRANCE AREA AND INSTALL CONSTRUCTION ENTRANCE. ROUGH GRADE THE AREA AREA ADJACENT TO MOUNTAIN ROAD FOR LINE-OF-SIGHT IMPROVEMENT. STABILIZE SLOPES.
- 7. ROUGH GRADE DRIVE AND SHOULDERS.
- 8. INSTALL NEW UTILITY POLE AND CONDUITS TO TOWER SITE.
- 9. STABILIZE DRIVEWAY SHOULDER AREAS .
- 10. INSTALL STORM DRAINAGE AND STONE SWALE.
- 11. INSTALL DRIVEWAY BASE AND SURFACE MATERIAL. 12. INSTALL TOWER AND ASSOCIATED IMPROVEMENTS. THIS WORK TO BE DONE BY OTHERS.
- 13. PAVE DRIVEWAY AS SHOWN.
- 14. MAINTAIN EROSION AND SEDIMENT CONTROLS UNTIL SITE IS STABILIZED.
- 15. REMOVE ANY REMAINING EROSION CONTROLS.

Connecticut Guidelines for Soil Erosion & Sediment Control

Table 5. 5 Seed Mixtures for Permanent Seeding, well or excessively drained soils, no mowing

No.	Seed Mixture ¹	Lbs/Acre	Lbs/ 1,000 Sq. Ft.
	White Clover	10	0.25
	Perennial Rye Grass	2	0.05
5	Total	12	0.30
	Creeping Red Fescue	20	0.50
	Redtop	2	0.05
	Perennial Rye Grass	20	0.50
6	Total	42	1.05
7	Smooth Bromegrass	15	0.35
/	Perennial Ryegrass	5	0.10

No.	Seed Mixture ³⁴	Lbs/Acre	Lbs/ 1,000 Sq. Ft.
	Panicledleaf Tick Trefoil with inoculant ¹⁰	10	0.25
	Total	30	0.79
	Switchgrass	101	0.25
	Weeping lovegrass	3	0.07
8	Little Bluestem	101	0.25
	Total	23	0.57
	Creeping Red Fescue	10	.25
	Crown Vetch (Chemung, Penngift) with inoculant ¹⁰	15	.35
	(or Flatpea with inoculant ¹⁰)	(30)	(.75)
9	Tall Fescue or Smooth Bromegrass	15	.35
	Redtop	2	.05
	Total	42 (or 57)	1.00 (or 1.40)

¹ Wildflower mix containing New England Aster, Baby's Breath, Black Eye Susan, Catchfly, Dwarf Columbine, Purple Coneflower, Lance-leaved Coreopsis, Cornflower, Ox-eye Daisy, Scarlet Flax, Foxglove, Gayfeather, Rocky Larkspur, Spanish Larkspur, Corn Poppy, Spurred Snapdragon, Wallflower and/or Yarrow may be added to any seed mix given. Most seed suppliers carry a wildflower mixture that is suitable for the Northeast and contains a variety of both annual and perennial flowers. Seeding rates for the specific mixtures should be followed.

120 Chapter 5 – The Functional Groups and Measures

Connecticut Guidelines for Soil Erosion & Sediment Control

	Creeping Red Fescue	20	0.45
10	Redtop	2	0.05
	Crown Vetch with inoculant ¹⁰	15	0.35
	(or Flatpea with inoculant ¹⁰)	(30)	(0.75)
	Total	37 (or 52)	0.85 (or 1.25)
	Panicledleaf Tick Trefoil with inoculant ¹⁰	8	0.20
11	Crown Vetch with inoculant ¹⁰	15	0.35
	Creeping Red Fescue or Tall Fescue or Smooth Bromegrass	20	0.45
	Total	43	1.00
	Switchgrass	101	0.25
12 ²	Perennial Ryegrass	5	0.10
	Crown Vetch with inoculant ¹⁰	15	0.35
	Total	45	1.05
		•	


			Lbs/
No.	Seed Mixture ³⁴	Lbs/Acre	1,000 Sq. Ft.
16	Tall Fescue	20	0.45
	Flatpea with inoculant ¹⁰	30	0.75
	Total	50	1.20
	Total	100	2.30
21	Creeping Red Fescue	40	0.90
	Tall Fescue	20	0.45
	Total	60	1.35
	Panicledleaf Tick Trefoil	2.0	0.05
	Total	13.5	0.33


² Considered to be a warm season mix.

121 Chapter 5 – The Functional Groups and Measures

Eversource | CT Information & Requirements 2024

Metering For Secured Locations





STORM DRAINAGE NOTES:

1. STORM SEWER PIPE TO BE AS NOTED:

CORRUGATED POLYETHYLENE PIPE CORRUGATED POLYETHYLENE PIPE PERFORATED CORRUGATED POLYETHYLENE PIPE WITH A SMOOTH INTERIOR C.P.E.P.-S CORRUGATED POLYETHYLENE PIPE WITH A SMOOTH INTERIOR, PERFORATED

POLY VINYL CHLORIDE REINFORCED CONCRETE PIPE

- C.P.E.P.-S PIPE TO HAVE BELL-AND-SPIGOT CONNECTIONS WITH A RUBBER GASKET MEETING ASTM F477. WHERE PIPE IS NOTED AS "WATER-TIGHT, IT SHALL MEET THE REQUIREMENTS OF ASTM D3212 AND ASTM F1417.
- 3. PVC GRAVITY SEWER PIPE 4" TO 15" IN DIAMETER, SHALL BE ASTM 3034 TYPE PSM POLY (VINYL CHLORIDE)(PVC) SEWER PIPE AND FITTINGS, DESIGNATION SDR 35. PVC GRAVITY SEWER PIPE 18" TO 24" IN DIAMETER, SHALL BE ASTM F679 TYPE PSM POLY (VINYL CHLORIDE)(PVC) SEWER PIPE AND FITTINGS, DESIGNATION SDR 35. PIPE JOINTS TO BELL-AND-SPIGOT TYPE AND SHALL COMPLY WITH ASTM D-3212 SPECIFICATION FOR JOINTS FOR DRAIN AND SEWER PLASTIC PIPES USING FLEXIBLE ELASTOMERIC SEALS.
- CONSTRUCTION OF STORM DRAINAGE SYSTEMS SHALL NORMALLY BEGIN AT THE DOWNSTREAM END AND PROCEED UPSTREAM.
- ALL LOCATIONS, INCLUDING SWALES, LAWN/LANDSCAPED AREAS, DETENTION BASINS, AND OTHER STORM SEWER DISCHARGE POINTS, THAT ARE TO RECEIVE A CONCENTRATED FLOW OF STORMWATER, ORIGINATING FROM SURFACE FLOW OR STORM SEWER SYSTEMS, SHALL BE STABILIZED AND PROTECTED FROM EROSION PRIOR TO RECEIVING THE WATER.

GEOTEXTILES AND EROSION CONTROL MATTING (ECM)

- UNLESS OTHERWISE INDICATED, GEOTEXTILES AND EROSION CONTROL MATTING (ECM) SHALL BE APPROVED FOR USE BY CONNDOT FOR THE INTENDED USE. REFER TO THE FOLLOWING DOCUMENT: "QUALIFIED PRODUCTS LIST FOR CONNECTICUT DEPARTMENT OF TRANSPORTATION PROJECTS, JUNE 2015," AS AMENDED.
- GEOTEXTILES AND EROSION CONTROL MATTING (ECM) SHALL BE INSTALLED AS PER THE MANUFACTURERS'


Town Engineer Town of Granby 15 North Granby Road Granby, CT 06035 Project: Proposed Communications Tower	Kevin Clarl		(860) 844-5318
15 North Granby Road Granby, CT 06035	0		townengineer@granby-ct.gov
Granby, CT 06035	Town of Gr	anby	
	15 North G	anby Road	
Project: Proposed Communications Tower	Granby, CT	06035	
	Drojecti	Dronocod Communications Tower	

Test Holes for refusal depth only

7/30/2025

TEST#	Soil Data	Percolation Rate
DP 0+50 €	Ledge @ 96"	
DP 1+00 &	Ledge @ 74"	
DP 1+50 €	Ledge @ 54"	
DP 2+00 ₺	Ledge @ 18"	
DP 3+00 ₺	No Ledge to 55"	
DP 9+00 ₺	No ledge to 58"	
DP 10+00 &	No ledge to 58"	





SCALE: NONE DATE NO. DESCRIPTION REVISIONS


NOTES & DETAILS TOWN OF GRANBY ACCESS DRIVE TO COMMUNICATIONS TOWER 239 MOUNTAIN ROAD **GRANBY. CONNECTICUT**


JOB #: 2023.G04 SHEET: 5 OF 6 DATE: September 5, 2025


TOWN OF GRANBY ENGINEERING DEPARTMENT **GRANBY TOWN HALL**

15 NORTH GRANBY ROAD


GRANBY, CONNECTICUT 06035 PHONE: (860) 844-5318 FAX: (860) 844-5325







Section 11 - Page 59 2018 I&R Book



1. Install 36" D x 36" H round handhole, SPC H-020, and fiberglass cover, SPC C-710. 2. Install conduit, with all joints cemented, through knockout to 4 inches inside handhole. Terminate conduit run with end bell (e.g., Item #500680 for 3-inch diameter). Conduit destination to be permanently marked on conduit end. Conduit shall be minimum 3-inch-diameter, Schedule 40 PVC. Limit four 4-inch-diameter conduits per knockout.

3. Gaps around conduit at knockout openings shall be sealed with cement mortar to prevent backfill from entering

- 4. Install a $^{1}/_{4}$ -inch-diameter nylon pull line in each duct, including 10 feet of slack, and secure to conduit plug (e.g., Item #526340 for 3-inch diameter). Plugged conduit to be left accessible.
- 5. Install on virgin or well tamped gravel. Where poor soil exists, remove to 6 inches below bottom of handhole and backfill with compacted clean gravel, free of foreign matter and debris, and extending 12 inches past edge of structure. Remaining backfill shall not contain ashes, frozen material, debris or stones larger than 2 inches in
- maximum dimension.


submersible.

6. When installing cable, utilize pulling eyelets provided in handhole. 7. Galvanized steel ground rods to be installed in trench adjacent to handhole. See **DTR 56.221**. 8. For loadbreak junction connector installation, refer to **DTR 50.111** for pad–mounted or **DTR 50.269** for

DIRECT-BURIED IN CONDUIT - INSTALLATION OF HANDHOLE SINGLE-PHASE CABLE - LOADBREAK JUNCTION CONNECTOR

CONSTRUCTION STANDARD

COVER - HANDHOLE - HEXAGONS AND ROUND 42-INCH DIAMETER MATERIAL SPECIFICATION SPC C-710 3 - EVERSOURCE ENERGY



PAD - PRECAST CONCRETE - TRANSFORMER 4/23/70 167 KVA MAXIMUM – 42" X 48" X 4"

MATERIAL SPECIFICATION

SPC P-009 11


SCOPE - All direct-buried primary cables shall be of the jacketed type. The cables may be random-laid with the secondaries and other utilities under certain conditions, detailed in DTR 44.101.

INSTALLATION IN TRENCH - All direct-buried cables shall be installed at a depth of at least 30 inches in the

following order:

1. Ensure that the bottom of the trench is well-tamped and free of rocks. 2. Install the conduit, gluing all couplings.

- 3. Install secondaries and other utility cables or conduits in the trench.
- 4. Backfill with 12 inches clean fill not to contain stones larger than 2 inches in maximum diameter.
- 5. Install cable warning tape 12 inches over the conduit. 6. Fill in the remainder of the trench with native backfill.
- 7. Install pull line, including 10 feet of slack, and secure to conduit plug at each end of conduit run.



THIS DETAIL ALSO USED FOR SINGLE PHASE CONDUITS


1. The trench shall be backfilled immediately following placement of the conduit. 2. 1/4-inch-diameter nylon pull line and plastic conduit plugs to be supplied and installed by contractor.

THREE-PHASE PRIMARY CABLE INSTALLATION DIRECT-BURIED - IN CONDUIT APPROVED


12/18/00

NORTHEAST UTILITIES CONSTRUCTION STANDARD DTR 51.102 | 3 Eversource | CT Information & Requirements 2024

Modular Meter Panels For Group Metering



- 1. Service load disconnects may be located above, below, or beside meter.
- 2. Individual meter sockets for meter packs require individual barriers to be purchased and installed by the Customer with provisions for seals and barrel locks.
- 3. For single and three phase 120/208 volt network and 277/480 volt services, the entire bank shall be cold sequenced.
- 4. When modular metering is 277/480 volts, each individual socket shall be cold sequenced.
- 5. Sketch of meter panel arrangements must be submitted to the Company for approval prior to layout and installation of equipment.
- 6. Refer to Metering for labeling requirements.
- 7. The grounding electrode conductor connection shall be made at an accessible location in the service equipment and not in the meter socket.
- 8. Bollards are required when there is a potential for damage by vehicles. Refer to Metering for required clearances.



| DTR 50.107 | 3

NOTES & DETAILS TOWN OF GRANBY ACCESS DRIVE TO COMMUNICATIONS TOWER 239 MOUNTAIN ROAD **GRANBY, CONNECTICUT**

SCALE: NONE DATE: September 5, 2025 JOB #: 2023.G04 SHEET: 6 OF 6



TOWN OF GRANBY ENGINEERING DEPARTMENT

GRANBY TOWN HALL 15 NORTH GRANBY ROAD **GRANBY, CONNECTICUT 06035** PHONE: (860) 844-5318 FAX: (860) 844-5325

- EVERSOURCE ENERGY